No.	Items of work	Per	Quantity
30	Burnt stone slabs, (Using old stones available including conveying from Yedatore Old Town and fixing).	S.ft.	93
31	Honne wood work wrought and put up	C.ft.	39·37
32	Roofing with first class Mangalore Tile on teak-wood reapers 2" by 1".	Sqr.	5·95
33	Ridge tile set in mortar	R.ft.	35
34	Honne wood battened door	S.ft.	18
35	Honne wood windows plain with iron bars and wire gauze ...	,,	48
36	Whitewashing	Sqr.	14·93
37	Flooring with concrete and plastering over	,,	3·00
38	Constructing parapet wall ornamental including carnice plastering etc., complete 2' height.	R.ft.	392
39	Size stone in mud	C.ft.	284
40	Teak wood work labour charges only for fixing (including wood oiling.).	,,	6·75
41	Pucca terrace roofing with brick on edge, two courses of flat tiles concrete plaster, etc.	Sqr.	0·81
42	Fixing covering slabs for Anjaneya Temple (fixing charges only)	S.ft.	60
43	Three inches concrete and chunam plastering over the roof ...	,,	60
44	Constructing ornamental parapet wall over the portico and Anjaneya Temple for a height of 1½'.	R.ft.	32
45	Erecting 2 stone pillars (old) for portico	Each	2
46	Stone pillars 1' by 1' by 1'	,,	2
47	Coping over beam 6" thick	R.ft.	10
48	Cement pointing to walls	Sqr.	3·73
49	Covering beams	Each	41
50	Covering pillars small	,,	26
51	Covering pillars big (in Anjaneya temple)	,,	4
52	Covering capitals	,,	26
53	Dismantling terrace	Sqr.	0·81

K. NARAYANA IYENGAR,
Executive Engineer,
Gauging and Upper Channels Division,
Mysore.

WATER SUPPLY DIVISION, BANGALORE.

Notice dated 28th November 1927.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, Bangalore, up to 4 P. M., of 15th December 1927, for carting from time to time about 2,000 bags of *Sulphate of Alumina*, each bag weighing about two cwts, from :—(1) the City Railway Station to the Stores of this office, (2) from the Stores to the Combined Jewel Filters, Malleswaram, Bangalore City, (3) from the City Railway Station to Combined Jewel Filters, Bangalore City, for the period from the 15th December 1927 to 31st December 1928.

2. Tender presented after due time will not be considered.

3. Each tender should be superscribed "Tender for Carting Sulphate of Alumina and to be opened on the 15th December 1927."

4. The consignment is to be cleared immediately after it is passed by the Goods Department.

5. The bags should be delivered in the same condition as they were received by the Goods Department.

6. The final acceptance of the tender will rest with the Executive Engineer, Water Supply Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. The name of the successful competitor whose tender has been accepted, will be posted on the "Notice Board" in the usual course.

8. The quantities are not guaranteed.

9. The contractor will be held responsible if any demurrage is to be paid owing to delay in carting the bags in time.

H. R. VENKATASUBBA RAO,
Executive Engineer.